



NOTES:

1. CONSTRUCTION JOINT SHALL BE INSTALLED AT THE MID-POINT BETWEEN EXPANSION JOINT SO CURB SEGMENT LENGTH WILL BE TEN (10) FEET).
2. PREMOLDED BITUMINOUS EXPANSION JOINT SHALL BE INSTALLED BETWEEN CURB SEGMENT TO SCALE EVERY TWENTY (20) FEET.
3. MATCH EXPANSION JOINT IF CURB IS INSTALLED ADJACENT TO SIDEWALK OR CONCRETE PAVEMENT.
4. CURB SEGMENT LENGTH MAY DIFFERENTIATE AT CLOSURE POINT TO SCALE, BUT SHALL NOT BE LESS THAN FOUR (4) FEET.
5. CURB SHALL CONFORM TO NYSDOT ITEM NO. 609.0304.
6. CAST-IN-PLACE CONCRETE CURB SHALL BE USED IN AREAS WHERE MONOLITHIC CURB AND SIDEWALK CONSRUCTION IS NOT REQUIRED AND/OR FEASIBLE (e.g. ADJACENT TO LAWN AREAS).

VILLAGE OF MAMARONECK
STANDARD CONSTRUCTION DETAILS

PREPARED IN THE
OFFICE OF THE
VILLAGE ENGINEER

CAST-IN-PLACE CONCRETE CURB

DESIGNED BY: ARC, PE CHECKED BY: ARC, PE
DRAWN BY: ARC, PE VOM Concrete Curb.dwg



VILLAGE OF MAMARONECK
VILLAGE MUNICIPAL BUILDING
169 MT. PLEASANT AVENUE (3RD FLOOR)
WESTCHESTER COUNTY
VILLAGE OF MAMARONECK, NY 10543
PHONE: (914) 777-7731
FAX: (914) 777-7792

PROJECT: DETAILS
SCALE: NOT TO SCALE
DATE: 03/13/2014

SD-5A