
PIN 8761.65 Hillside Avenue Bridge Replacement

Over the Mamaroneck River Village of Mamaroneck, Town of Mamaroneck, Town of Rye

Westchester County, NY

Public Informational Meeting October 23, 2017 - 7:30 PM















Agenda



- Introduction of Project Team
- Meeting Overview
 - Format and Purpose of Meeting
 - How to Provide Comments
- Project Location
- Project Background
- Technical Highlights
 - Data Collection, Existing Conditions and Needs
 - Design Considerations & Challenges
 - Preliminary Layout
- Project Process & Schedule
- Open Floor for General Questions
- Discussion with Individuals Regarding Specific Concerns

Tri-Municipal Team



Village of Mamaroneck

- Robert Yamuder Village Manager
- Daniel Sarnoff Assistant Village Manager
- Hernane DeAlmeida Superintendent of Public Works & Village Engineer

Town of Mamaroneck

- Stephen Altieri Town Administrator
- Robert Wasp Town Engineer

Town of Rye

- Thomas Nardi Town Councilman
- Debbie Reisner Chief of Staff
- John Decrescenzo Highway Superintendent

Consultant Team



HVEA Engineers

- Jack Gorton, P.E. Project Manager
 - Overall project oversight, reviews, Federal compliance
- Jared Anderson, P.E. Project Engineer
 - Day to day project activity, client contact, design oversight
- Matthew Erbacher, E.I.T. Design Engineer
 - Design, report & plan preparation, estimation

Firm Background

- Formed in Beacon, NY in 2001 by three former NYSDOT Region 8 Engineers
- Supported by design staff in Chestnut Ridge, NY
- Focus on infrastructure projects for municipalities
 - Specializing in Federally-Aided projects

Project Location





Meeting Overview




- Public Informational Meeting
- Federal Funding Requirement
- Develop a better understanding of the project site
- Get a sense of local and individual concerns

How to Provide Comments



- Please Sign In
- Comment Sheet
- Comment Verbally
 - On the record at end of this presentation
- Provide individual comments after meeting
- Project Email:

hillsidebridge@vomny.org



Continuous Public Involvement



- Project Team will always be available
- Meetings with individual property owners
- Progress materials delivered to the Team
- Monthly project meetings with the Team









Project Background



- ■Bridge was constructed in 1936
- Bridge and approach channel walls are deteriorating
 - NYS Rating = 4.33 out of 7 (2015 Report)
- 2017 Inspection Report forthcoming
- ■Village applied for BRIDGE NY Funding in 2016
 - Awarded \$3.0 million to cover design and construction
 - 95% is reimbursable cost to municipalities is \$150k
 - Split three ways \$50,000 per municipality

Project Background



- US Army Corps of Engineers began reevaluating the Mamaroneck and Sheldrake Rivers in 2007
 - Following an April 2007 nor'easter which caused \$50 million of damage in the Village
- Corps completed a Final Environmental Impact Statement (FEIS) in April 2017
- Contains numerous recommendations, including a wider, deeper Mamaroneck River channel.
 - HVEA will be incorporating the relevant recommendations to the best extent practicable



FINAL ENVIRONMENTAL IMPACT STATEMENT
FOR THE
MAMARONECK AND SHELDRAKE RIVERS
FLOOD RISK MANAGEMENT
VILLAGE OF MAMARONECK, WESTCHESTER COUNTY,
NEW YORK
GENERAL RE-EVALUATION REPORT

U.S. ARMY CORPS OF ENGINEERS NEW YORK DISTRICT ENVIRONMENTAL ANALYSIS BRANCH JACOB K. JAVITS FEDERAL BUILDING NEW YORK, NEW YORK 10278-0090

APRIL 2017


Project Objectives



- Replace the structurally deficient bridge
- •Incorporate USACE's recommendations
- Respect aesthetic / historic character
- Minimize disruption to the public
- Maintain budget and schedule

Existing Conditions





North Fascia

Existing Conditions






North Sidewalk Deterioration

Data Collection



So far, HVEA has performed or obtained:

- Topographic Survey
- Property Research
- Evaluation of Existing Conditions
- Soil / Rock Borings
- •Utility Inventory
- ■Threatened & Endangered Species Review
- State Historic Preservation Office (SHPO) Review
- US Coast Guard Consultation
- Traffic Counts
- Speed Data
- Accident Data



Traffic, Speed and Accident Data



Traffic Counts and Speed Data

- Taken via ATR (tube counter)
- August 14 18, 2017 & September 18 25, 2017
- No appreciable increase after Labor Day
- AADT = 1,222 vpd
- 85th Percentile Speed = 27.8 mph

For comparison

 AADT of Mamaroneck Avenue = 19,630 vpd (Westchester County website, June 2012)

Accident Data

- 3 accidents in 3 year study period (4/1/14 to 3/31/17)
- None directly attributed to the bridge (NYSDOT ALIS request, via NYSDMV)

Project Design Standards and Specifications



- NYSDOT Bridge Manual
- NYSDOT Highway Design Manual
- PROWAG Public Rights-of-Way Accessibility Guidelines
 - Subset of ADA (Americans with Disabilities Act) regulations
- NYSDOT Standard Specifications for Construction and Materials

Design Considerations



- SEQR Type II
 - No significant adverse environmental impact
- Maintain or increase "low chord" elevation
- Widen bridge opening to the extent practicable
 - Design goal is 40 feet
- Provide deeper foundations per USACE
 - Future deepening of Mamaroneck River
 - Between 1 ½ to 2 feet
- Roadway geometry to remain the same
- Re-use existing stone facing for new structure, where practical


Project Challenges



- Tight project constraints
 - Residential neighborhood
 - Underground and overhead utilities
- Protect and support sanitary sewers
 - County 66" diameter
 - Village 8" diameter
- Detour during construction
 - Full closure of Hillside Avenue
 - Allows for longer work days, safer operation
 - Allows project to be completed quicker than staged / traditional methods
- Ensure Mamaroneck River is protected from erosion, construction debris and hazardous materials

Preliminary Layout





Preliminary Bridge Types





Con/Span

Preliminary Bridge Types





SpaanSpan

Preliminary Bridge Types





NEXT Beam

Federal Aid / NYSDOT Process



- Federal Funding
 - ■95% Federal \$2,850,000
 - ■5% Local \$150,000
- NYSDOT Oversight
 - Acts on FHWA's behalf
- Overview of Process
 - Prepare Design Report for Agency Review
 - Obtain Design Approval & Proceed to Final Design
 - Right of Way Clearance
 - Submit Final Plans, Specifications, Estimate for Approval
 - Approval to Advertise for Bidding
 - Approval to Award to Responsible Low Bidder
 - Notice to Proceed with Construction

Project Schedule



- ■Project Start Date June 15, 2017
- Submit Draft Design Report and Preliminary Plans December 2017
- Obtain Approval to Begin Final Design April 2018
- Final Design Submission for Village Review July 2018
- ■Plans, Specs & Estimate (PS&E) for State Review August 2018

Project Schedule



- Project Bidding by October 15, 2018
- ■Project Award must occur by December 15, 2018
 - Condition of BRIDGE NY Funding
 - 18 months from Start Date of June 15, 2017
- Construction to occur in 2019

Questions & Concerns?

Thank you from The Village of Mamaroneck, Town of Mamaroneck, Town of Rye & HVEA Engineers











hillsidebridge@vomny.org